

## Technical Memorandum

**To:** Mr. Mark Lipan  
**From:** Sheila D. Rayman, P.E.  
**Date:** 11/12/2021  
**Re:** 2022 Englewood Drive Improvement Project Addendum 1

---

1. This addendum modifies the following:

Improvement Plan Sheet 2, Material Specification, last paragraph: Remove the reference to No. 10 limestone backfill. Note shall read:

REFER TO TRENCH AND BEDDING DETAILS IN PLANS FOR BEDDING AND BACKFILL SPECIFICATIONS FOR ALL STORM SEWER, SANITARY SEWER, WATER MAIN AND LATERALS INSTALLED UNDERNEATH EXISTING OR FUTURE PAVEMENT. COMPACT BACKFILL IN 6" LIFTS. THE MINIMUM COMPACTION REQUIREMENT SHALL CONFORM TO ODOT ITEM 203. COMPACTION TESTS ARE REQUIRED BY THE VILLAGE OF SILVER LAKE AT THE CONTRACTOR'S EXPENSE

2. This addendum clarifies:

There were no pavement cores or subsurface borings performed within Englewood Drive.

---

End of memorandum